Bruhath Bangalore Mahanagara Palike

"BTS for Kind Approval"

Name of the Work:- Executing AV Street light,dimer switches and control wire at ward no-43

Sl. No	Approx. Qty	Description	Unit	Approved Rate		Rate quoted by contractor	
				in Figures	in words	in Figures	in words
		KPWD (Ele) S.R.2010-11					
1	90000	Fabricating supplying and mounting MS box made out SWG suitable for floor/wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer pain and finally finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete b) 16 SWG	sqdm	0.30	Rupees Zero Only Paise Thirty Three Only		
2	12	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers etc., complete c) 63 Amps	Each	219.00	Rupees Two Hundred and Nineteen Only		
3	12	Supplying and fixing Microprocessor based Astronomical timer switch with using necessary bolts, nuts and washers etc.,	Each	7515.00	Rupees Seven Thousand Five Hundred and Fifteen Only		
4	12	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, energy cross-3 with short circuit breaking capacity of 10K and Complete wiring as required. b) 40-63 Amps SP 1) Group 'A'	Each	370.00	Rupees Three Hundred and Seventy Only		
5	12	a) 5-32 Amps SP 1) Group 'A'	Each	195.00	Rupees One Hundred and Ninety Five Only		
6	12	Supply and fixing of 4 pole power contactor with NO/NC contacts on existing wood/panel board using necessary bolts, nuts, washers and wiring etc., complete with AC-3 Rating and as per IS-13947. c) 60-70 Amps	Each	3865.00	Rupees Three Thousand Eight Hundred and Sixty Five Only		
7	12	Supplying and fixing angle iron frame work fabricated out of M.S angle iron... and M.S. flat... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint. (32.9a) a) 40x40x6mm	Rmtr	240.00	Rupees Two Hundred and Forty Only		
8	120	Supplying of LT UG cable having aluminium conductor PVC insulated, sheathed, galvanized, steel wire/steel tap armoured cable with PVC outer sheathing 1.1KV Class/ Class 'A' PVC Cable c) 4 core 16sqmm	per mtr	150.00	Rupees One Hundred and Fifty Only		

04-05

14

9	120	Labour charges for laying of 1.1 KV class U/G cable in existing trench of pipe stoneware pipe/ on wall/ on pole as required.It. On wall /Structure a) 5 sqmm to 16sqmm	Rmtr	18.00	Rupees Eighteen Only		
10	80	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes f) 15 sqmm	Each	14.00	Rupees Fourteen Only		

I am prepared to take up the above work at the rates quoted in the Schedule 'B'

CONTRACTOR

EXECUTIVE ENGINEER (Ele)
DASARAHALLI ZONE, BBMP

"DTS APPROVED"